

ESTIMATION FOR SOCIETY DRAINAGE WORK

Sr.No.	Description of work	Approx Quantity	Unit	Rate	Amount
A	INSIDE SOCIETY DRAINAGE WORK				
	LABOUR WORK				
1	Manual Excavation	43.75	brass	2400	105000
2	Tractor breaker for PCC & rock breaking work	2	Days	4000	8000
3	Tractor Trip for Debris material shifting outside	15	trip	1500	22500
4	Paving block removing, shifting & stacking	1500	Sq.ft	10	15000
5	Department labour	8	M/C	600	4800
6	Bobcat for material shifting & debris loading in tractor trip	24	Hrs	800	19200
7	Paving block fixing work	1500	Sq.ft	20	30000
8	8" RCC line Plumbig work	450	R.ft	60	27000
	Round Chamber Brick work	7	No.	5500	38500
	Hanching work	60	No.	60	3600
9	Hand roller compactor	1	Days	4000	4000
B	OUTSIDE SOCIETY DRAINAGE WORK AT ROAD AREA				
	LABOUR WORK				
1	Manual Excavation	40.25	brass	2400	96600
2	Tractor breaker	4	Days	4000	16000
3	Tractor Trolly	15	trip	1500	22500
5	Department labour	6	M/C	600	3600
6	Bobcat	8	Hrs	900	7200
		Labour Amount =			423500
		Area of work in Sq.ft =			8400
		Rate per Sq.ft =			50.42
C	SOCIETY DRAINAGE WORK				
	MATERIAL				
1	8" RCC pipe NP3 class	70	Nos.	650	45500
2	Cement	35	bag	310	10850
3	6" Fly ash bricks	4000	No	12	48000
4	Crush sand	3	brass	3100	9300
5	20mm Aggregate	1	brass	2900	2900
6	Round chamber frame & cover	7	No	2200	15400
7	M15 concrete for PCC 100mm thk. Below PCC work, excavated road area	13	cum	3500	45500
		Material Amount =			177450
		Area of work in Sq.ft =			8400
		Rate per Sq.ft =			21.13
				Total Material + Labour Amount =	600950
				Rate per Sq.ft =	71.54