

SAIGURU INFRASTRUCTURE LLP

All types of Painting & Polishing Work

To,		Address: Flat No 8, Premvarsha Apartment, S. No. 44 Bibvewadi, Pune 37.
	Tingre Reality work	Pratap Shilimkar Mobile No: 9422321771

	Kondhva, Pune				
					DATE

QUOTATION WITH MATERIAL PAINTING WORKS

	Sr.No.	Item Description	Unit	Rate	PAINT
		INTERNAL PAINT			
		Process for Int Paint : Sanding ,one coat oil primer			
		2/3 coat birla/JK putty,2/3 coat acrylic putty,sanding			
		1coat oil/water primer,putty touchup 1 coat paint			
		Putty touchup and final coat paint			
a)	1)	Luster Paint Plain Finish	SQ.FT	30.00	asian,n
	2)	Luster Texture Finish	SQ.FT	35.00	
	3)	Luster Paint Dark Colour	SQ.FT	55.00	
	4)	Luster Paint (1" to 3")	R.FT	20.00	
	5)	Luster Paint Grove	R.FT	15.00	
b)	1)	Water base Luster paint	SQ.FT	38.00	
		Water base Luster paint patti -1" to 3"	R.FT	25.00	
		Water base Luster paint patti -grove	R.FT	20.00	
c)	1)	Royal Finish Paint	SQ.FT	45.00	asian,n
	2)	Royal Finish Paint (1" to 3")	R.FT	25.00	
	3)	Royal Finish Paint Grove	R.FT	20.00	
d)	1)	Oil Paint	SQ.FT	20.00	asian,n
	2)	Oil Paint Matt Finish	SQ.FT	35.00	
	3)	Satin Finish Paint	SQ.FT	28.00	
e)	1)	Plastic Paint	SQ.FT	25.00	asian,n
f)	1)	Oil Bond Synthetic	SQ.FT	10.00	asian,n
	2)	Oil Bond Acrylic	SQ.FT	14.00	
g)	1)	Jotun Fenamestic Gold (Hygiene)	SQ.FT	55.00	
	2)	Jotun Fenamestic Gold (1" to 3")	R.FT	38.00	
	3)	Jotun Fenamestic Gold Grove	R.FT	28.00	
	4)	Jotun Fenamestic Gold Cornice (1" to 3")	R.FT	95.00	
	Tip-	Same rate applicable as per sqft for Wall paint Rft -4" to 11"			
g)	1)	Jotun Fenamestic Reach Matt	SQ.FT	52.00	
	2)	Jotun Fenamestic Reach Matt (1" to 3")	R.FT	38.00	
	3)	Jotun Fenamestic Reach Matt Grove	R.FT	28.00	
	4)	Jotun Fenamestic Reach Matt Cornice (1" to 3")	R.FT	105.00	
	Tip-	Same rate applicable as per sqft for Wall paint Rft -4" to 11"			
		INTERNAL POLISH			
		Process for Polish : 2/3 type paper sanding,3/4 coat			
		sealer,filling putty nail hole,sanding & matching			
		colour 2/3 coat of floor melamine/melamine			

b)	1)	Melamine Malaysian	SQ.FT	120.00	Melamine
	2)	Melamine Malaysian patti (1" to 3")	R.FT	70.00	
	3)	Melamine Malaysian patti (4" to 6")	R.FT	90.00	
	4)	Melamine Malaysian Grove	R.FT	45.00	
	5)	Melamine Malaysian Cornice (1" to 3")	R.FT	145.00	
c)	1)	Italian Malaysian	SQ.FT	150.00	Italian
	2)	Italian Malaysian patti (1" to 3")	R.FT	95.00	
	3)	Italian Malaysian patti (4" to 6")	R.FT	120.00	
	4)	Italian Malaysian Grove	R.FT	65.00	
	5)	Italian Malaysian Cornice (1" to 3")	R.FT	175.00	
		POLY COAT (P.U)			
		Process for Polyurethane : 2/3 type paper sanding,			
		2/3 coat epoxy ,filling putty nail hole,sanding &			
		matching colour, 2/3 coat of clear / colour PU.			
a)	1)	Poly Coat (P.U) Clear	SQ.FT	250.00	asian, I
	2)	Poly Coat patti (P.U) (1" to 3")	R.FT	110.00	
	3)	Poly Coat patti (P.U) (4" to 6")	R.FT	190.00	
	4)	Poly Coat (P.U) Grove	R.FT	75.00	
	5)	Poly Coat (P.U) Molding (1" to 3")	R.FT	150.00	
b)	1)	Poly Coat (P.U) Pigmented	SQ.FT	275.00	asian, I
	2)	Poly Coat patti (P.U) Pigmented (1" to 3")	R.FT	145.00	
	3)	Poly Coat patti (P.U) Pigmented (4" to 6")	R.FT	195.00	
	4)	Poly Coat (P.U) Pigmented Grove	R.FT	95.00	
	5)	Poly Coat (P.U) Pigmented Molding (1" to 3")	R.FT	185.00	
		Pu Addi. buffing Extra rate Rs.60 per Sqft	Sqft	60.00	
		RUBIO MONO COAT (RMC)			
	1)	Rubio Mono Coat (RMC)	SQ.FT	175.00	Rubio Mono
	2)	Rubio Mono Coat (RMC) Patti (1"-3")	R.FT	95.00	
	3)	Rubio Mono Coat (RMC) Molding (1"-3")	R.FT	115.00	
	4)	Rubio Mono Coat (RMC) Grove	R.FT	65.00	
	1)	Rubio Mono Coat (RMC) Bio Matt	SQ.FT	250.00	
	2)	Rubio Mono Coat (RMC) Patti (1"-3") Bio Matt	R.FT	115.00	
	3)	Rubio Mono Coat (RMC) Molding (1"-3") Bio Matt	R.FT	110.00	
	4)	Rubio Mono Coat (RMC) Grove Bio Matt	R.FT	55.00	
		DUCO PAINT			
		Process for Duco : Fill up holes,2/3 Coat epoxy, 2/3			
		coat filler,2/3 coat PS White/grey,putty touchup			
		sanding, and 3/4 coat paint.			
a)	1)	Duco Paint	SQ.FT	200.00	as
	2)	Duco Paint patti (1" to 3")	R.FT	90.00	
	3)	Duco Paint Molding (1" to 3")	R.FT	110.00	
	4)	Duco Paint patti (4" to 6")	R.FT	150.00	
	5)	Duco Paint Grove	R.FT	45.00	
b)	1)	Duco Paint Metallic	SQ.FT	450.00	Asian ,N
	2)	Duco Paint patti Metallic With P.U (1" to 3")	R.FT	200.00	
	3)	Duco Paint Metallic Grove	R.FT	90.00	
	4)	Duco Paint patti Metallic (4" to 6")	R.FT	250.00	
	5)	Duco Paint Metallic Molding (1" to 3")	R.FT	225.00	

d)	1)	Epoxy Paint	SQ.FT	200.00	as
e)	1)	Water Base P.U	SQ.FT	400.00	
		LAMINATION			
		Process for lamination : 2/3 type paper sanding, 3/4 coat epoxy ,filling putty nail hole,sanding & matching colour, 2/3 coat of epoxy, 9/10 coat Lamination,buffering with 60-3000 no papers & buffer			
a)	1)	Lamination Indian	SQ.FT	450.00	I
	2)	Lamination Indian patti (1" to 3")	R.FT	250.00	
	3)	Lamination Indian patti (4" to 6")	R.FT	350.00	
	4)	Lamination Indian Grove	R.FT	165.00	
	5)	Lamination Indian Molding (1" to 3")	R.FT	280.00	
b)	1)	Lamination Italian	SQ.FT	550.00	I
	2)	Lamination Italian patti (1" to 3")	R.FT	320.00	
	3)	Lamination Italian patti (4" to 6")	R.FT	375.00	
	4)	Lamination Italian Grove	R.FT	220.00	
	5)	Lamination Italian Molding (1" to 3")	R.FT	375.00	
	Tip-	Lamination Italian Pigmented-50 rs rate extra for all items			
		SPECIAL EFFECT TEXTURE			
a)	1)	Oikas - Stucco	SQ.FT	175.00	(
	2)	Oikas Stucco waterproof	SQ.FT	275.00	
	3)	Concrete Finish Texture	SQ.FT	250.00	
	4)	Liquid Metal Paint(Brass,Copper ,Branz,Alluminium)	SQ.FT	3500.00	
		EXTERNAL PAINT			
a)	1)	Apex Ultima	SQ.FT	20.00	/
	2)	Apex Ultima Protect	SQ.FT	22.00	
b)	1)	Whether Shield Max	SQ.FT	20.00	I
	2)	Whether Shield Power Flex	SQ.FT	24.00	
c)	1)	Texture Ruff / Tuff	SQ.FT	35.00	
	2)	Dholupur Stone Texture	SQ.FT	75.00	
	3)	Spray Coat Finish Texture	SQ.FT	95.00	
		Dholupur Stone Texture bricks pattern	SQ.FT	95.00	
a	1)	Scaffolding Bamboo	SQ.FT	12.00	
	2)	Scaffolding MS	SQ.FT	16.00	
	3)	Masking & Covering Charges Laminare,Flooring & Glass	SQ.FT	25.00	
	4)	Cleaning Charges Laminare,Flooring & Glass	SQ.FT	20.00	
Note:	1)	GST WILL BE EXTRA			
		Realise 25% advance against workorder			
		Validity of quotation is for 5 months from date of submission there fore the rate revision AT 10% automatically take place			
	A	After 10ft height rates will increase by x1.5 times			
	2)	Labour Rooms,Light, Water providing your scope			
	3)	Windows & Flooring Masking,covering			
		Material provide to your scope			
		THANK YOU !			

SAIGURU INFRASTRUCTURE